

KONTROL ENGLINEERING LTD. 1090 Augusta Ave., Burnaby, B.C. V5A 4V2 TEL. FAX 604 291 7434 CELL;604 723 7534

Engineer to receive at least 48 hours notice for inspections:

After the reinforcement for the foundation works has been completed

See Soils Report

3.0 kPa

After the roof framing works have been completed.

P Eng. Seal

Structural Notes General:

- 1) All works to conform to the latest edition of the B.C. Building Code 2006.
- 2) This drawing is to be read with
- a) City of Coquitlam Standard Specifications and with
- b) Forum Projects Ltd. Box 32120 Walnut Grove P.O. Langley B.C. V1M 2M3 (604)-888-6672 (o) (604)-888-7857 (f) drawings for City of Surrey Parks, Recreation & Culture TE Scott Park Washroom _____-148th Street. Surrey
- 3) Advance Precast Ltd 884 Stremel Rd, Kelowna, B.C. V1X 3E6 250-765-1431 (Ph) 250 765 6658 (Fax) Drawings for TE Scott Park Washroom____-148th Street. Surrey
- 4) DESIGN LOADS
- a) S Allowable Soil Bearing Pressure
- b) Ground Snow Load
- c) Rain Load
 - 0.3 kPa
- d) Wind Load 0.47 kPa
- e) Seismic: S(a): 0.2 = 1.0 S(a): 0.5 = 0.69 S(a): 1.0 = 0.33 S(a): 2.0 = 0.17

1. F(a) = 1.1 R(d) = 2.0 R(a) = 1.5

Mackin Park Washroom Structural **Details** [Issued for Construction June 1st 2012] Civic: 1046 Brunette Ave. Coquitlam B.C.