



Addendum No. 1
City of Coquitlam
Tender No. 85263
Storm and Sanitary Main CIPP Repairs
 (Consists of 1 Page)

Issue Date: June 20, 2025

Questions & Clarifications

- Q1) Would the City consider installing full length liners instead of Spot Repairs?
- A1) The City will consider installing full length liners for spot repair locations only if it does not incur additional costs to the City. Full length liner installations must include reinstating all lateral connections with grout packer as well as providing submissions listed in MMCD Section 33 05 24, CURED IN PLACE PIPE LINERS, Clause 1.5.**
- Q2) What is the CIPP sample frequency requirement for spot repairs? (Ie. each spot repair, every 5 spot repairs, etc.)
- A2) For spot repairs, the Contractor is to provide 5 total samples for all spot repair locations listed in the Form of Tender – Appendix 1 - Schedule of Quantities and Prices (Pay Items 6.01 – 6.45). Locations for the 5 samples will be determined by the Contract Administrator (CA). The CA may request additional samples if initial samples fail. Costs for preparation and provision of samples for Quality Control are considered incidental to the CIPP Repair price.**
- Q3) Would like to request the CCTV footage as per Section 00 72 43S, 1.07 Location of Existing Utilities.
- A3) See “Appendix C – Reference Documents” for QFile download links to CCTV videos, reports, and as-builts to all pipe segments listed in the Tender.**

End of Addendum No. 1

Tenderers shall take into account the content of this Addendum in the preparation and submission of the Tender which will form part of the contract and should be acknowledged on the Tender form where indicated.

Upon submitting a Tender, Tenderers will be deemed to have received all addenda and considered the information for inclusion in the Tender submitted.

Issued by:

M. Pain
 Manager Procurement
 Email: bid@coquitlam.ca